



**OFFICE OF THE EXECUTIVE ENGINEER (220 KV GSS)
RAJ. RAJYA VIDHYUT PRASARAN NIGAM LTD., NAGAUR**

Phone No. 01582-240888 E-mail: xen.220.nagaur@rvpn.co.in
(REGD. OFFICE:-VIDHYUT BHAWAN, JANPATH, JYOTI NAGAR JAIPUR-302005)

"AN ISO 9001:2000 CERTIFIED COMPANY"

NO.:RVPNL/XEN/220 KV/GSS/NGR/F...../D. 732 /DATED 14.02.2017

All Registered contractors

T&C Ajmer Zone.

Sub: - Consent for restringing of broken earth wire of 220 KV Nagaur - Barsingsar line.

Dear Sir,

In ref. to subject cited above it is intimated that the work of restringing of broken earth wire of 220 KV Nagaur - Barsingsar line is to be carried out on CLRC against TN-3768.

Interested contractors are requested to give their consent within a period of 7 days i.e. upto 3.00 PM of 21.02.2017.

Encl: - 'G' Schedule.

Thanking you.

Yours faithfully

Executive Engineer

220 KV GSS Nagaur

Copy submitted to the Superintending Engineer (T&C) RVPNL Merta city for kind information & publication on RVPN portal.

Executive Engineer

220 KV GSS Nagaur

"G" SCHEDULE


Name of work :- **Restranging of broken earth wire of 220 KV Nagaur - Barsingsar line.**

Ref :- 1. BSR No. RVPN/ SE/TLPC/XEN/TL-4A/BSR/D. 2054 DT. 27.08.2008

2. CLRC No. RVPN/ SE/TLPC/Steel/A.III/TN-3768/D. 81/3330 DT. 28.02.2013

S. No.	Particulars	Unit	Unit rate in Rs.	Quantity	Amount
1	Restranging of earth wire Dismantling of earth bond, vibration dampers, declipping & fitting in rollers, de-tensioning, holding & lowering of earth wire, adding / removing and jointing of Earth wire, lifting into rollers and re-tensioning, jointing, clipping & fitting of vibration dampers & earth bond per route KM of the section to be restrung. Dismantled material not re-used to be deposited in our stores & stacked.				
	(ii) One no. 7/4.00 mm Galvanised wire	KM	4361.00	3.5	15263.50
	Total				15263.50
	CLRC @ 69% above BSR (Ajmer area CLRC chapter (i)(a)(b))				10531.815
	G. Total				25795.32


Junior Engineer(M)
220 KV GSS Nagaur


Assistant Engineer(M)
220 KV GSS Nagaur


Executive Engineer
220 KV GSS Nagaur