



Office of The Assistant Engineer 132 KV GSS RVPNL,  
Sadul Shahar Dist.Sri Ganganagar 335062 Ph. 01503-223925

Email-aen.132.sadulshahar@rvpn.co.in

No. - RVPNL/AEN/132KVGSS/SDS/Tech./2016-17/F. / D259 Dated 09.09.2016

To

(All enlisted contractors under RVPN Jodhpur zone)

M/S .....  
.....  
.....  
.....

Registration No.....

**Subject :- Acceptance for Restranging work of Earth wire of 132KV RIICO Sri Ganganagar - Sadulshahar Tr. Line between Loc. No. 84 to 91 and 97 to 99 at 132 KV GSS RVPNL Sadul Shahar on CLRC rates as per G schedule.**

On the above cited subject it is informed that the Restranging work of Earth wire of 132KV RIICO Sri Ganganagar - Sadulshahar Tr. Line between Loc. No. 84 to 91 and 97 to 99 to be executed at 132KV GSS RVPNL Sadulshahar on CLRC rates as per G-schedule.

As you are the registered firm in the office of S.E. (T&C) RVPNL Hanumangarh for this work, so you are requested to please give your acceptance/consent for above said work as per G schedule enclosed within 15 days. If your acceptance till aforesaid time frame is not received in this office, it will be under stood that you are not interested in doing this work.

Encl. :- Copy of G - Schedule

  
Assistant Engineer  
132 KV GSS RVPNLtd.  
Sadul Shahar

Copy submitted to the following for information & necessary action please :-

- 1 - The Superintending Engineer ( T&C ) RVPNL Hanumangarh.
- 2 - The Executive Engineer ( 220 KV GSS ) RVPNL U V Sri Ganganagar.
- 3 - The Feeder Manager ( T&C ) RVPNL Bikaner.
- 4 - The Accounts Officer (T&C) RVPNL, Hanumangarh
- 5 - E-mail address- verma.subhash@rvpn.co.in


  
Assistant Engineer  
132 KV GSS RVPNLtd.  
Sadul Shahar

## G-Schedule

Name of Work :- RESTRINGING WORK OF EARTH WIRE OF 132 KV RIICO SRIGANGANAGAR- SADULSHAHAR LINE FROM LOC. NO. 84 TO 91 & LOC. NO. 97 TO 99 .

S.N o.	Particulars	Unit	Qty.	Rate	Amount
1	Restringing of Earthwire:				
A	Dismantling of earth bond, vibration dampers, declipping & fitting in rollers, de-tensioning, holding & lowering of Earthwire, adding/ removing and jointing of Earthwire, lifting into rollers and re-tensioning. jointing, clipping & fitting of vibration dampers & earthbond per route KM of the line section to be restrung. Dismantled material not re-used to be deposited in our stores & stacked.				
	(i)One No. 7/3.15mm galvanised wire	KM	2.722	6713.00	18272.79
	Total				18272.79
				Above 64%	11694.58
				G. Total	29967.37
	Say				29967.00

The above G-schedule has been prepared as per new BSR issued by Superintending Engineer (TLPC) Jaipur vide letter No./ RVPN/ SE/ TLPC/ XEN/ TL-A4/BSR/D. 856 Dated 25.06.2015

  
Junior Engineer (M)  
132 KV GSS RRVPNL  
Sadul Shahar

  
Assistant Engineer  
132 KV GSS RRVPNL  
Sadulshahar