

RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LTD.
(Regd. Address: Vidhyut Bhawan, Jyoti Nagar, Jaipur.)
OFFICE OF THE SUPERINTENDING ENGINEER (T&C)
RRVPN, JODHPUR.

Email : se.tnc.jodhpur@rvpn.co.in
No. RVPN/SE/T&C/M/S.PS./F. /2017-2018/D1463 /Dated 14/07/2017
NOTICE INVITING BID

NIB No.: 16


Bid Security: Rs. 780/-

Subj:- Painting of 132/33 kV Transformers (2 Nos.), other equipments & steel structures installed at 132 kV GSS Mandore.

Single stage Bids are invited from the Eligible & Experienced contractors for painting of 132/33 kV Transformers (2 Nos.), other equipments & steel structures installed at 132 kV GSS Mandore. Please quote your lowest rates in the form of percentage as per attached "G" schedule.

TERMS & CONDITIONS:

1. The Prices shown in the "G" schedule is inclusive of all type of labour charges, but exclusive of service tax, sales tax & insurance etc. Any variation in the taxes/duties or any other taxes will be intimated to the contractor in time through RVPN web site www.energy.rajasthan.gov.in/rvpnl.
2. Bid documents are available at RVPN web site (www.energy.rajasthan.gov.in/rvpnl). Bid documents will also be provided in the working days.
3. Bid security Rs. 780/- shall have to be deposited with bid in cash or through DD in favour of Accounts Officer (T&C), RVPNL, Jodhpur.
4. Rates should be quoted in sealed cover before due date of opening.
5. The work is to be start within 15 days from the issue of the work order.
6. Work should be carried out as per technical specification enclosed with bid documents.
7. If the work will not be completed within the specified time, penalty as usual shall be imposed.
8. Your offer will remain valid for 90 days.
9. Bid received late on any account shall not be considered.
10. Bid should reach this office by 3.30 PM on dated 21.07.2017 & shall be opened on the same day at 4.30 PM in the presence of the representative of firms who may wish to attend.
11. The undersigned reserve the right to reject any or all bids without assigning any reason.
12. Payment will be made after completion of work & on presentation of bill as per the procedure given here under:-
 - (a) Payment equal to 100% (in case contractor furnished performance security deposit by crossed Bank Draft or by way of bank guarantee).
 - (b) 90% (In case contractor furnished as undertaking for deduction of performance security amount from his each running & final bill @ 10% of the amount of bill) of the total value of work will be paid against monthly running bills to be submitted to the in charge of work.
13. The quantum of the work can be changed as per site requirement.
14. This NIB governed as per RTPP rules 2013.


Superintending Engineer (T&C)
RVPN, Jodhpur.


Copy forwarded to the following for information & necessary action.

1. The Zonal Chief Engineer (T&C) RVPN, Jodhpur.
2. The Executive Engineer (400 kV GSS) RVPN, Jodhpur.
3. The Feeder Manager O/o SE (T&C) RVPN, Jodhpur for uploading on RVPN website.
4. Notice Board.


Superintending Engineer (T&C)

RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED
G Schedule for painting of 132/33 kV Transformers (2 Nos.), other equipments & steel structures
installed at 132 kV GSS Mandore UNDER NIB - 16
(As per BSR for Repair & Maintenance work of EHV Lines & GSS applicable from 01.04.2017)

Code No.	Description	Unit	Rate (Rs.)	Qty.	Amount (Rs.)	Remarks
2.1	PAINTING OF UNPAINTED STEEL STRUCTURES: Aluminium painting of unpainted steel structures at the GSS including paint and painting brush, emery paper, cloth & solvents etc. The surface shall be first cleaned with wire brush/emery paper and thereafter wiped with cloth to remove rust and dust or any other deposits on erected M.S. steel structures & beams. One coat of red oxide paint shall be applied after carrying out cleaning and allowed to dry. Thereafter, two coats of aluminum paint shall be applied. Each subsequent coat shall be applied only after the previous coat has dried up. The paint used shall be from any of the following recognized manufactueres, namely Asian/Nerolac/Berger/Johnson Nichoison.	SQ. Metre	42	60	2520.00	
2.2	PAINTING OF OLD PAINTED STEEL STRUCTURES: Aluminium painting of old painted steel structurcs at the GSS including supply of paint and painting brush, emery paper, cloth & solvents etc. The surface shall be first cleaned with wire brush/emery paper and thereafter wiped with cloth to remove rust and dust or any other deposits on erected M.S. steel structures. Two coats of aluminum paint shall be applied. applied. Each subsequent coat shall be applied only after the previous coat has dried up. The paints used shall be from any of the following recognized manufactueres, namely Asian/Nerolac/Berger/Johnson Nichoison.	SQ. Metre	32	100	3200.00	
2.3	PAINTING OF TRANSFORMERS & EQUIPMENTS: Enamel painting on power transformers & other equipments including supply of paint & spray painting set, emery paper, cloth & solvents, etc. at GSS by cleaning surface thoroughly with soda/washing with water. Thereafter, two coats of smoke gray synthetic enemel paint shall be applied by spray method. Each subsequent coat shall be applied after the previous coat has fully dried up. The paints used shall be from any of the following reconized manufacturers, namely Asian/Nerolac/Berger/John Nicholson. In case of surface area of radiators, those fins will only be considered which are actually leasible and approachable for painting by spray or by brush.	SQ. Metre	33	1000	33000.00	
TOTAL					38720.00	


Superintending Engineer (T&C)
RVPNL, Jodhpur

I/We agree % above/below of G schedule

Name of Firm/Contractor

Signature & Date