

RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED



Corporate Identity Number (CIN) : U40109RJ2000SGC016485

Regd. Office: Vidyut Bhawan, Jyoti Nagar, Jaipur-302005

OFFICE OF THE EXECUTIVE ENGINEER (T&C)

132 KV GSS Campus Sindhari Road, BARMER-344001

Telephone No. 02982-221178 Email Address: - xen.cm.barmer@rvpn.co.in website: -rvpn.co.in

No- RVPN/XEN/ T&C/BME /Estt./F-40 / D. 425 Dated. 27.01.2017

All Register Contractors
Jodhpur Zone

SHORT TERM TENDER NOTICE

For Emergency Stringing work for Const of One Circuit LILO from 220 KV D/C Ramgarh-Dechu line at 220 KV GSS Amarsagar. Tender shall be received up to 2.00PM on 06.02.2017 and shall be opened at 3.00PM on the same day in presence of bidders who choose to be present at that time. The G schedule of the work of Emergency Stringing work for Const of One Circuit LILO from 220 KV D/C Ramgarh-Dechu line at 220 KV GSS Amarsagar is enclosed. All the enclosed documents shall be returned duly filled up with signature/date/seal on each page.

1. Specification No.: - RVPN/XEN/T&C/ SHORT TERM NIT
2. Name of work: - Emergency Stringing work for Const of One Circuit LILO from 220 KV D/C Ramgarh-Dechu line at 220 KV GSS Amarsagar
3. Estimate Cost: - Rs. 95000.00
4. Completion period: - 15 Days
5. Due Date of opening: - 06.02.2017 at 3.00PM
6. Earnest money: - NIL

TERMS AND CONDITIONS FOR SUPPLY

1. The tender should be addressed to the Executive Engineer (T&C), RVPN, having office at 132 KV GSS Campus Sindhari Road, Barmer. Email id is xen.cm.barmer@rvpn.co.in and contact No. is 9414061192, Sh. K. L. Gajraj XEN (T&C), RVPN, Barmer
2. The tender shall be submitted in closed/sealed envelope duly super scribe as "Tender for Emergency Stringing work for Const of One Circuit LILO from 220 KV D/C Ramgarh-Dechu line at 220 KV GSS Amarsagar
3. The under does not blind himself to accept the lowest or any other tender and Reserve the right to reject any or all tender's without assigning any reason thereof.
4. The quoted rates shall be valid for 120 days from the date of opening tenders.
5. The work shall be completed as per "G" schedule within 45 days from the date of placing of work order/LOI or within 10 days after issue of complete material, whichever is later.
6. 100% payment shall be arranged/released as per Nigam's payment policy on completion of work as per specification through RTGS by the Accounts Officer (T&C), RVPN, Jaisalmer after receipt of verified bills/Invoice by the consignee.
7. All addition and/or alterations in the tender must be clearly initialed.

8. The Rate's should be quoted the FIRM prices inclusive of all taxes and duties, insurance, and other related cost both in words and figures.
9. Tender received late due to any reason or which are incomplete shall not be accepted for consideration.
10. Quantity of items may vary at the time of placement order.


Encl: As Above


27.1.2017

(Er. K. L. Gajraj)
Executive Engineer (T&C)
RVPN, Barmer

Copy submitted/forwarded to the following for information & necessary action please.

1. The Zonal Chief Engineer (T&C), RVPN, Jodhpur
2. The Superintending Engineer (T&C), RVPN, Barmer/Jodhpur/Bikaner/Jaisalmer /Sirohi/Ramgarh/Kakani/Bhadla/Ratangarh
3. The Accounts Officer (T&C), RVPN, Jaisalmer with requested to please instruct to your any Representative to attend this office on the date i.e 06.02.2017 of opening of the tender
4. The Assistant Engineer (T&C), RVPN, Barmer
5. The Feeder Manager (T&C), RVPN, Sirohi along with details of LIMITED TENDER and G Schedule to upload on Nigam website
6. Notice Board


27.1.2017

Executive Engineer (T&C)
RVPN, Barmer

RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED
OFFICE OF THE ASSISTANT ENGINEER (T&C) RVPN BARMER

G Schedule for Emergency work of Construction of 220 KV D/C LILO Ramgarh-

| S. No. | Particulars | Unit | Rate | Qty. |
|--------|---|---------|------|-------|
| 1 | CONDUCTOR STRINGING: - | | | |
| | (B) Stringing of ACSR Zebra including hoisting of insulator string, laying, jointing & tensioning of conductor, clamping with armour rods and fixing of vibration damper per route KM of the line. | | | |
| | (i) 1 Conductor for Ist Circuit (Loc. No. 13 (DB+0) to 26 (DC+0) | Per Job | | 1 |
| | (ii) 1 Conductor for IInd Circuit (Loc. No. 13 (DB+0) to 22 (DB+0) | | | |
| 2 | ERECTION OF SUB STATION STRUCTURE: - | | | |
| | Erection of substation structures including leveling, setting of stub & tightening, punching of nuts& bolts and tack welding upto beam level as per specification. (2 Nos of 220 KV D/C TTb & 2 Nos. 220 KV D/C TTA crossArm) | Job | | 1 |
| 3 | CONDUCTOR STRINGING: - | | | |
| | (B) Stringing of ACSR Zebra including hoisting of insulator string, laying, jointing & tensioning of conductor, clamping with armour rods and fixing of vibration damper per route KM of the line. | | | |
| | (i) 3 Conductor for S/C Line | KM | | 0.045 |
| 4 | EARTH WIRE STRINGING: - | | | |
| | (A) Stringing of galvanised steel Stranded wire laying, jointing & tensioning of conductor, clamping, clipping and fixing of vibration damper and earth bond etc. | | | |
| | (i) One No. 7/3.15mm galavnised wire | KM | | 0.045 |



Executive Engineer (T&C)
RVPN, BARMER


Assistant Engineer (T&C)
RVPN, Barmer