




CHAPTER-24

REPLACEMENT OF 11 KV CT PT SETS

Chapter Code No	DESCRIPTION OF WORK	UNIT	Rate/ Unit
1	2	3	4
24.1	Safe Loading of new/old 11 KV CT PT sets (all sizes)	Set	128.14
24.2	Safe unloading of new /old 11 KV CT PT set (all sizes )	Set	57.24
24.3	Installation , testing as per Nigams norms & commissioning of new 11KV CT PT set (all sizes) on erected supports including jumpering, crimping of lugs/ clamping earth connection of body & conducting pre commissioning test before energization and satisfactory operation in all respect	Set	748.98
24.4	Removal of damaged 11 KV CT PT Set from existing structures	Set	524.23
24.5	Replacement of defective/burnt 33 KV or 11 KV CT/PT/CTPT set (All sizes) at 33/11 S/S. It includes installation, testing, commissioning with jumpering, crimping of lugs/clamping earth connection of body.		
(a)	33 KV or 11 KV CT/PT/CTPT set	Nos.	1273.21
(b)	33 KV CT/PT/CTPT set	Nos.	1273.21
24.6	Transportation or 33 KV or 11 KV CT/PT/CTPT set (All sizes) for replacement at 33/11 KV S/S alongwith their loading & un-loading.		
	33 KV or 11 KV CT/PT/CTPT set		
(a)	Within 10 KMs.	Nos.	194.19
(b)	Above 10 Kms. and upto 30 Kms.Add per each km,or part thereof	Kms.	5.55
(c)	Above 30 Kms. and upto 50 Kms.Add per each km,or part thereof	Kms.	3.76

**NOTE: The Rates are inclusive of all applicable Taxes/ Duty except service tax which will be paid extra by Nigam if applicable.**

 AEN(TW)       XEN(TW)

 Sr. A.O.(TW)  
3

 SE(TW)