	AJMER VIDYUT VITRAN NIGAM LIMITED (Turn-Key Works Circle)
	Corporate Identification Number (CIN)- U40109RJ2000SGC016482
	Regd. Off. Vidyut Bhawan, Panchsheel Nagar, Makarwali Road, Ajmer-305004
	Phone & Fax: 0145-2644507, Email: setwavvnl@gmail.com, Website: www.avvnl.com

No. AVVNL/ CE (TW-MM)/SE (TW)/ XEN-I/AEN-III/2015-05/CLRC /D 70

Date:-

- 1 JUN 2015

The Superintending Engineer (ACC/ADC/ O&M),
 AVVNL, Ajmer/Udaipur/Banswara/Rajsamand
 Chittorgarh/Nagaur/Sikar/Bhilwara/Jhunjhunu/
 Dungarpur/Pratapgarh

Sub: - Amendment / addendum in Central Labour Rate Contract (BSR)-2014.

- Ref: -
1. This office letter no. AVVNL/CE (TW-MM)/SE/TW/CLRC/D. 994 dated 08.09.2014
 2. This office letter no. AVVNL/CE (TW-MM)/SE/TW/CLRC/D. 1462 dated 16.12.2014
 3. This office letter no. AVVNL/CE (TW-MM)/SE/TW/CLRC/D. 1534 dated 05.01.2015
 4. This office letter no. AVVNL/CE (TW-MM)/SE/TW/CLRC/D. 1535 dated 05.01.2015
 5. JPD/SE(TW)/XEN(TW-I)/R-APDRP/CLRC/D. 4380 dated 27.03.2015


In continuation with above mentioned letters the following amendment of some items/ works in chapter code 6.23 of Central Labour Rate Contract (BSR)-2014 is made hereunder:-

Chapter code No.	Existing Clause			Amendment Clause		
	Description of work	Unit	Rate/ Unit	Description of work	Unit	Rate/ Unit
6.23	Erection of LT Distribution pillar Boxes of 800/400/160/100 Amps. capacity. Each 37"x24" base as per JVVNL standard including excavation, bricks, sand, cement masonry of size 4"x3"x10" and 3' in ground and 1 1/2' above road level with muffing to support and mounting the pillar. The masonry will have 4" X 4" opening 2" below ground level two in the rear side and one each in the remaining sides to facilitate entry and exist of incoming and outgoing PVC cable. Earthing of the pillar shall be connected to DP earth with 7/10 SWG stay Wire & lugs.			Erection of LT Distribution/ LT pillar Boxes of 800/400/160/200/100 Amps. Capacity Each 37"x24". base as per JVVNL standard including excavation, bricks, sand, cement masonry of size 4"x3"x10" and 3' in ground and 1 1/2' above road level with muffing to support and mounting the pillar. The masonry will have 4" X 4" opening 2" below ground level two in the rear side and one each in the remaining sides to facilitate entry and exist of incoming and outgoing PVC cable. Earthing of the pillar shall be connected to DP earth with 7/10 SWG stay Wire & lugs.		
6.23.1	800 Amp.	Nos.	2739.49	Upto 400 Amp.	Nos.	2451.81
6.23.2	400 Amp.	Nos.	2451.81	Above 400 Amp. to 800 Amp.	Nos.	2739.49
6.23.3	160 Amp.	Nos.	2451.81			
6.23.4	100 Amp.	Nos.	2451.81			

The above amendment bears the approval of Hon'ble MD, AVVNL, Ajmer.

XRS/ID
 876


SE (IT), AVVNL, AJMER
 R. R. No. 618 Dt. 01/06/15
 SECTION.....


 (S.S. MEENA)
 Dy. CHIEF ENGINEER (TW-MM)
 AVVNL, AJMER

P.T.O.

Copy submitted / forwarded to the following for information and necessary action:-

1. The Chief Engineer (O&M/M&P/Plan/IT), AVVNL, Ajmer/Udaipur/Jhunjhunu.
2. The Dy. Chief Engineer (Comml.)AVVNL, Ajmer.
3. The Chief Account Officers (ATB/R&C/IA/W&M/),AVVNL, Ajmer/Jaipur.
4. The Superintending Engineer(M&P/Plan/MM/Civil/IT/Comml./RGGVY),AVVNL, Ajmer
5. The secretary (Admin.),AVVNL, Ajmer
6. The ASP (Vig.) ,AVVNL, Ajmer.
7. TA to MD, AVVNL, Ajmer.
8. The Executive Engineer (O&M) AVVNL,
9. The Sr. Account Officers (MM-TW/Rev/Comml./Control/CPC), AVVNL, Ajmer.
10. The Account Officers (O&M)/ (ACC/ADC), AVVNL, Ajmer / Sikar / Nagaur / Jhunjhunu / Chittorgarh/Bhilwara/Udaipur/Rajasmand/Banswara/Dungarpur/Pratapgarh.
11. PA to MD, Ajmer Discom for kind perusal to MD, Ajmer Discom.
12. PA to Director (Technical/Finance), Ajmer Discom for kind perusal to Director (Technical/Finance), Ajmer Discom.


 Dy. CHIEF ENGINEER (TW-MM)
 AVVNL, AJMER