



AJMER VIDYUT VITRAN NIGAM LIMITED
(COMMERCIAL WING)

No. AVVNL/Dy.CE(Comml.)/XEN-II/F-57(F)/2011/D.3611 Ajmer, Dt 13/11/2012

Comml. AJ-481

ORDER

Sub:- Regarding Levy of overhead charges in preparing estimates for MPs/MLs/BADPs aided development works.

The proposal for levy overhead charges in preparing estimates for MPs/MLAs/BADPs aided development works was placed before 29th Discoms Coordination Forum meeting held on 14.11.2011, wherein it was decided that the estimates in such cases be prepared on actual basis in terms of electrical and civil charges indicating composite rate of each item to cover supply and fixing the material both. The Sample estimate of 11KV line is however enclosed as Annexure-'A' for the guidance of the field officers, which is based on latest store issue rates.

It is enjoined upon all concerned to ensure compliance accordingly.

This order is issued in suppression to the previous Order Comml AJ-108 dated 29.08.2002 and shall come into force with immediate effect.

By Order

(G.R. Choudhary)

Dy. Chief Engineer (Comml.)

Copy to the following for information and necessary action:-

1. The Zonal Chief Engineer (O&M), AVVNL, Jhunjhunu/ Udaipur/ Ajmer.
2. The Secretary (Admn.), AVVNL, Ajmer
3. The Chief Accounts Officer(Account/Audit/Revenue), AVVNL, Ajmer
4. The Superintending Engineer (O&M), AVVNL, -----with----- Nos. of _____ spare copies for circulating among field officers.
5. The Superintending Engineer (M&P/Plan/MM/RDPPC), AVVNL, Ajmer/Udaipur/Jaipur.

6. The Superintending Engineer(IT), AVVNL, Ajmer for uploading the above circular on website.
7. The Addl.S.P. (Vig), AVVNL, Ajmer.
8. The Company Secretary, AVVNL, Ajmer
9. Shri P.N. Bhandari, IAS (Retd.), Jaipur
10. Sh.D.S. Agrawal, Rudraksh Energy, Jaipur
11. Dr. K.L.Jain, Honorary Secretary, Raj Chamber of Commerce & Industry, Jaipur
12. Secretary General, Consumer Unity & Trust Society, ('CUTS'), Jaipur
13. Chief Electrical (General) Engineer, O/o the G.M. (North), Jagatpura, Jaipur
14. Rajasthan Vidhyut Vikas Sansthan,, Vaishali Nagar, Jaipur
15. The Executive Engineer (), AVVNL, -----
16. The Sr.Accounts Officer (), AVVNL, -----
17. The Incharge of Legal Section AVVNL, Ajmer.
18. The Public Relation Officer, AVVNL, Ajmer.
19. The TA to MD, AVVNL, Ajmer.
20. The PA to Chairman Discoms Jaipur.
21. The PA to MD, Jodhpur Discom, Jodhpur.
22. The PA to Director (Finance / Technical), AVVNL, Ajmer.



Dy. Chief Engineer (Comml.)

Comd J-481

Endl of Comm. AJ-		Annexure-'A'			
AJMER VIDYUT VITRAN NIGAM LIMITED, AJMER					
Sample Estimate of 11KV, 1KM Line on 8 mtr. PCC Poles with 60 mtr. Span					
Including material cost & erection charges					
S.NO.	Description	Unit	Composite Rate		
			S/C Line Weasel Conductor Qty. Amount (Rs.)		
1.	PCC Poles 8m long	Nos.	1849.29	21	38835.09
2.	11KV Cross Arm with Top Hamper and clamps	Nos.	890.34	19	16916.46
3.	11KV line DP structure set	Nos.	6275.73	2	12551.46
4.	11KV Pin Insulator	Nos.	43.65	60	2619.00
5.	11KV GI Pin	Nos.	83.595	60	5015.70
6.	11KV Disc Insulator (B&S) Type 45KN	Nos.	407.01	18	7326.18
7.	11KV Disc H/W (B&S) Type	Nos.	559.725	18	10075.05
8.	ACSR Weasel Conductor	Km	26036.19	3.1	80712.19
9.	GS Earth Wire 6SWG	MT	59512.5	0.155	9224.44
10.	GS Stay Set 20 x 2400 MM	Nos.	1100.205	14	15402.87
11.	GS Stay Wire 7/8SWG	MT	87906.72	0.3	26372.02
12.	MS Nut and Bolt(AS)	Kg	87.24	50	4362.00
13.	MS Earthing Set (Rod Type) with wire & clamps	Nos.	679.83	10	6798.30
14.	11KV Stay Insulator	Nos.	26.745	14	374.43
15.	PG Clamp for Weasel	Nos.	58.65	18	1055.70
16.	M.S. Angle 50x50 MM	MT	70252.35	0.07	4917.66
17.	Danger Plate	Nos.	73.97	5	369.83
	Total				242928.38
			Say in lacs of Rs.		2.43

Note:- 1. Amount against civil works if any shall be charged on actual basis.

2. For retrieved material of line (Which may or may not be removed a credit @ 25% of estimated amount shall be allowed.

3. The composite rate of each item shall be considered & charged as per prevailing rates in accordance with Standard

Issue Rate.

4. No other charges like Supervision charges contingencies etc shall be charged in above estimate.