



AJMER VIDYUT VITRAN NIGAM LIMITED

(Commercial Deptt.) (Website-www.avvnl.com)

Corporate Identification Number (CIN)-U40109RJ2000SGC016482

Regd. Off. Vidyut Bhawan, Panchsheel Nagar, Makadwali Road, Ajmer 305004

Tel No -0145 2644501 , Fax 01452644502, E-mail-cecommercialavvnl@yahoo.co.in

No. AVVNL/ CE(COMML)/XEN(C-II) /F./2015-16/D. *1048* Ajmer Dated *27-24-7-15-*

Comml. AJ-590

Order

Sub: Clarification regarding provision of Net Metering and Grid Connectivity of Grid Connected Rooftop and Small Solar Photovoltaic System.

Ref:- 1. RERC Net Metering Regulation-2015.

2. Comml AJ580 Dt. 06.05.2015.

3. RERC order dt. 30.06.2015.

The detailed guidelines & procedure for Net Metering and Grid Connectivity of Grid Connected Rooftop & Small Solar Photovoltaic system has been issued vide Comml AJ 580 dt 06.05.2015. Subsequently difficulties were reported in the implementation of the certain provisions of the regulation by the field officers and matter was referred to RERC for clarifications. The RERC vide their order dt. 30.06.2015 has clarified the same and accordingly these clarifications may be read in continuation to the Comml AJ 580 dt 06.05.2015 under respective clauses as under:-

1. In the clause F(2) table Sr.1 may be read as under :-

S.NO.	Connected Load Of Eligible Consumer	Connectivity level
1.	Upto 5 KW	240V- Single Phase /415V- Three Phase as per connectivity level

2. In the Annexure IX table Sr. no 5 may be read as under:-

(a) Meter for Solar Generation Measurements:-

S.NO.	Technical Parameters	Connectivity at 415V & below voltage level		Connectivity of above 415 V voltage level	
		Whole Current meters	CT Operated	CT-PT Operated	CT-PT Operated
		Solar Plant Capacity upto 4 KW	Solar Plant capacity above 4 KW and upto 15 KW	Solar Plant capacity above 15 KW and upto 50 KW	HT/EHV supply
5	Current rating	10-60	10-60	5 Amp.	5 Amp.

(b) Meter for Net Generation Measurements:-

S.NO.	Technical Parameters	Connectivity at 415V & below voltage level		Connectivity of above 415 V voltage level	
		Whole Current meters		CT Operated	CT-PT Operated
		Upto 5 KW connected load	Above 5 KW and upto 18.65 KW Connected load	Above 18.65 KW and upto 50 KVA contract demand	HT/EHV supply
5	Current rating	10-60	10-60	5 Amp.	5 Amp.


(B.M. Bhamu)
Chief Engineer (Comml.)