

RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED

[Corporate Identity Number (CIN):U40109RJ2000SGC016485]

Regd. Office: RVPN Rest House, Pur Road, Bhilwara -311001

O/O THE EXECUTIVE ENGINEER (T&C) RVPNL BHILWARA

E-mail: xen.tnc.bhl@rvpn.co.in

MOBILE: 9413382245

NO.RVPNL/XEN/(T&C)/RVPN/BHL/2017-18/F.Const work bay D: 92 DATE: 30.5.17

M/S _____

Limited Enquiry Tender Under This Office TN- 02 /2017-18

Notice Inviting Bids (NIB)

Limited Enquiry Tender Under This Office TN No-02/2017-18, are invited for construction works of following erection of-

S.N.	Particulars of works	Estimated cost	Tender cost	EMD Rs.	Last date for submission of BID.
1.	Erection of Galvanised steel structure, Laying of Earth mesh, Erection of equipment, Bus bar, Jumpers & Cable laying work etc at 132 KV GSS SUWANA BHILWARA for M/S Rajasthan Housing Board (deposite work)	Rs 58,000 /-	Nil	Rs 1,160/-	08.06.2017

Filled in/completed tenders/Bids are invited & shall be accepted latest by upto 2.00 PM of dated 08.06.2017 & receipted tenders shall be opened on same day i.e. dated 08.06.2017 At 3.00 PM.

1. We have read carefully all terms & conditions/ instructions of the tender specification & accepted the same as enclosed with this NIT.
2. Rates will remain valid upto the completion of work.
3. Other terms & conditions are enclosed.

Encl:- G-Schedule

EXECUTIVE ENGINEER(T&C)
RVPNL, BHILWARA

Copy forwarded/submitted to following for information:-

1. The Superintending Engineer (T&C) RVPN BHILWARA.
2. The AO(T&C) RVPN BHILWARA
3. The FM(T&C) RVPN, AJMER through email to upload NIT on website of Nigam
4. Notice Board.

EXECUTIVE ENGINEER(T&C)
RVPNL, BHILWARA

**'G' Schedule of Const. of 01 No. 33 KV Bay at 132 KV GSS Suwana Bhilwara for
M/s Rajasthan Housing Board (Deposit Work)**


Name of Office: AEN-1 (T&C) RVPN BHILWARA


Name of Work: Erection of Galvanized steel structure, Laying of earth mesh, Erection of equipment, Bus Bar, Jumpers & Cable laying work etc. at 132 KV GSS Suwana Bhilwara for 01 No. 33 KV Bay for M/s Rajasthan Housing Board

Reference : BSR AS ON 01.04.2017 VIDE RVPN/SE(Contracts-II)/XEN-4/F./D 45 JAIPUR Dated 21.04.17

S. N.	Item no. of BSR	PARTICULARS OF WORK	UNIT	QTY.	RATE	AMOUNT in Rs.
1	2	3	4	5	6	7
		EARTH MESH WORK				
	A-1	Laying earth mesh with 25mm / 28mm dia M.S. rod at a depth of 0.80 metre from top level of foundations, including excavation of trench of required depth and backfilling of the same, transportation of M.S. Rod from site store to location, welding of M.S. Rod to M.S. Rod along the length, at crossings and with earth electrodes as per drawing, application of bitumen impregnated tape on all welded joints, for the type of soil prevalent at 0.80 metre below top level of foundations (M.S. Rod of above sizes & M.S. Flat as required shall be made available by RVPN)				
		(a) In case electricity is made available by RVPN without charges				
1		i) Normal dry soil	Metres	100	24	2400
2		ii) Hard soil / Murram / Black cotton soil	Metres	100	26	2600
	B-1	Laying of earthing risers of 50x6 mm / 50x10 / 50x12 mm size M.S. Flat at a depth of 0.80 metre from top level of foundation, including excavation of trench of required depth and back filling of the same, transportation of M.S. Flat from site store to locations, preparation of risers, bending as per requirement (after heating if necessary), fixing on and welding / bolting / to equipment / structure and peaks of structures laying in the trench welding to the earth mesh of M.S. Rod as per drawing, including welding of extra length of M.S. Flat if required, application of bitumen compound and covering with bitumen impregnated tape on all welded joints, painting of all surfaces of risers above ground level with red oxide and green paint for the type of soil prevalent at 0.80 metre below top level of foundations (M.S. Rod of above sizes & M.S. Flat as required shall be made available by RVPN)				
		(a) In case electricity is made available by RVPN without charges				
3		i) Normal dry soil	Metres	100	27	2700
4		ii) Hard soil / Murram / Black cotton soil	Metres	100	28	2800
	C-1	Placing / Driving of earth electrode of 25 / 28mm dia. M.S. Rod of length 3.00 meters (approx) to a depth of 3.80 meters from the top level of foundations, including excavation of pit as required and back filling of the same transportation of M.S. Rod from site store to locations cutting of M.S. Rod to desired length preparation of one end as spike if necessary, welding of earth electrode to earth mesh of M.S. Rod as per drawing application of bitumen compound and covering with bitumen impregnated tape on all welded joints, for the type of soil prevalent at 3.80 metres below top level of foundation (M.S. Rod of above sizes & M.S. Flat as required shall be made available by RVPN)				
		(a) In case electricity is made available by RVPN without charges				
5		ii) Soft rock	Nos.	5	532	2660
6	2	ERECTION OF SUB-STATION STEEL STRUCTURES columns, beams, lighting mast and equipment structures (excluding Circuit Breakers and Capacitor Banks) of all types including transportation of structure member nuts & bolts, Washers, etc. from site store to locations, their assembly, placing on foundation, fixing of template, with foundation bolts as required levelling and preparing of grouting as required, but excluding grouting, erection after grouting and tightening & punching of nuts & bolts (Maximum height of structures up to 20 meters)	MT	4.5	2321	10444.5
		C/F				23604.5



Executive Engineer (T&C)
RRVNL BHILWARA



Assistant Engineer-I (T&C)
RVPNL, BHILWARA


JEN (T&C)
RRVNL BHILWARA

		B/F				23604.5
3		BUS- BAR WORK				
A		STRINGING of 220 KV, 132 KV, 33 KV & 11 KV Bus Bar of ACSR conductor, including transportation of conductor, disc insulators and tension hardware from site stores to location, laying and cutting required length of conductor. Cleaning and assembly of disc insulators as required along with fitting of bolted type or compression type tension hardware as made available (compression machine shall be provided by RVPN on rent free basis) . Making up at one end, stringing of conductors between the beams with specified sag and tension, also equalizing sag and fitting spacers and spacers T-clamps for twin conductor, for three phases of conductors in each bus-section.				
7		i) Single ACSR Panther	section	1	1165	1165
B		JUMPERS OF ACSR conductor (3 nos. Y- type) between bus to equipment or between equipment to equipment or between bus to bus, including transportation of conductor, disc insulators and hardware from site stores to locations, cleaning and assembly of disc insulators as required along with fitting of suspension hardware and erection as required, cutting required length of conductor, making connections, fixing of spacers & spacer T- clamps as required, tightening of clamps/ connectors, dressing, etc., for three phases.				
8		i) Single ACSR Zebra/ panther conductor	Set	8	333	2664
4		STRINGING of Earth wire (size 7/ 3.15mm or 7/ 4.00mm), including transportation of earthwire, tension hardwares, etc., from site store to locations, laying and cutting required length of earthwire fitting of bolted type or compression type hardware as made available (compression machine shall be provided by RVPN on rent free basis) making up at one end, stringing of earthwire between structure peaks with specified sag and tension jumpering and connecting earth bonds. For single earthwire.				
9			Each	4	292	1168
5		ERECTION OF SUB-STATION EQUIPMENTS				
B		Erection of Current Transformer /Potential Transformer / Capacitive voltage Transformer/ Series Reactor / Residual Voltage Transformer / Neutral Current Transformer with clamps & connectors on already erected steel structure including transportation from site store to locations. Fabrication of base frame, fixing of terminal connectors, tightening of nuts & bolts etc, complete in all respects.				
10		(iii) 33 KV CT/PT	Nos.	3	532	1596
C		Erection of lightning Arrestor on already erected steel structure including transportation of lightning arrestor , clamps & connectors surge counter etc. from site store to locations. fabrication of base frame, fixing of terminal connectors, surge counter, tightening of nuts & bolts etc. complete in all respects.				
11		iii) 33 KV	Nos.	3	317	951
D		Erection of Isolators on already erected steel structure including transportation of base frame P. I. "s. contacts. Mechanism box, clamps & connectors etc. from site store to locations. minor fabrication as required and fixing of terminal connectors etc , adjustment / alignment of isolator and its earth blade. If provided for their smooth operation and final adjustment if required after jumpering.				
		iii) 33 KV				
12		a) Without Earth Blade	Nos.	2	916	1832
13		b) With Single Earth Blade	Nos.	1	1364	1364
		C/F				34344.5



Executive Engineer (T&C)
RRVNL BHILWARA



Assistant Engineer-I (T&C)
RVPN, BHILWARA



JEN (T&C)
RRVNL BHILWARA

		B/F				34344.5
H		Erection of 33 KV or 11 KV Circuit Breakers, including transportation of equipment, structure members. Nuts & bolts, Clamps & connectors accessories etc. from site store to location assembly of support structure their placing on foundation leveling and preparing for grouting as required but excluding grouting assembly/ placing of poles. Mechanism box, etc. on support structure as per manufacturers drawings fitting of terminal connectors, etc. but excluding commissioning of CB				
14		i) 33 KV Outdoor type (VCB / SF 6)	Nos.	1	7404	7404
6		Erection of Control & Relay Panels complete in all respects including transportation from site store to control room, placing on foundation / cable trench as per layout, interconnection between control & relay panels and with existing panels, fixing of side / top covers and doors earthing to existing earth strip in control room, connection of bus wiring to existing panels and between control and relay panel. As required.				
15		ii) Simplex panel. DC Panel, RTCC Panel, PLCC Panel etc.	Nos.	1	632	632
7		Erection of Marshalling Kiosk /Line Matching Unit (LMU) / Line Matching & Distribution Unit (LMDU) complete in all respect including transportation from site store to location, placing on foundation / cable trench as per layout, preparing for grouting of foundation bolts but excluding grouting etc.				
16		ii) 33 KV or 11 KV marshalling Kiosk	Nos.	1	192	192
10		LAYING AND TERMINATION OF CABLES				
A		Control Cables				
		i) Laying of P.V.C. insulated unarmoured/ armoured control cables of 1.1 KV grade with copper conductor in cable trenches as per specification as required, including transportation of cable drums from site store to location laying in cable trenches, cutting to required length, placing them on cable racks/ cable trays/ & dressing. Including removing and re-fixing trench covers as required making necessary connections, testing, cable marking on both the terminal ends, etc. as required for all sizes from 2c x 2.5 sq. mm. to 20c x 2.5sq. mm. 4c x 4sq mm and 4c x 6sq. mm.				
17		a) Unarmoured control cable.	Mtrs	2500	5	12500
		ii) fixing of control cables in position with single compression nickel plated brass cable glands conforming to IS: 12943 & having three metal washers and one rubber ring, including preparation of cable and drilling of corresponding holes in gland plates etc. as required. & including cost of cable gland for each cable gland of size				
18		a) 19 mm unarmoured control cable	Nos.	30	44	1320
19		c) 25 mm unarmoured control cable	Nos.	4	67	268
		ii) Termination of wires of cables with copper conductor using copper terminal ends (pin or ring type as required of Dowells or equivalent make as approved by the Engineer-in charge) duly crimped with crimping tool, including making wire ends ready for crimping, ferruling & dressing of wires, etc. as required, including cost of terminal ends for all wires for each cable at both ends for cables of the following sizes				
20		c) 4c x 2.5 sq. mm	Each	5	43	215
21		f) 12c x 2.5 sq. mm	Each	2	128	256
		in case all the wires of any cable are not got terminated then a deduction at the rate of Rs. 6.00 shall be made for each end of the wires not terminated				
22		i) 4c x 4.0 sq. mm	Each	10	57	570
		in case all the wires of any cable are not got terminated then a deduction at the rate of Rs. 7.00 shall be made for each end of the wires not terminated				
TOTAL						57701.5

(Rs. Fifty Seven Thousand Seven Hundred Two Only)


 Executive Engineer
 RRVPNL BHIWARA


 Assistant Engineer-I (T&C)
 RVPNL, BHIWARA


 JEN (T&C)
 RRVPNL BHIWARA

Tenders are invited & shall be accepted latest by 2.00 pm on dated 08.06.2017 for the above NIT which shall be opened on same day dated 08.06.2017 at 3.00 pm

Name of Firm/Bidder. _____

Address _____

Phone No / Fax No _____

TIN/CST/RST No- _____

Name of contact person _____

Contact No/Mobile No _____

Date /___/___ _____

Place _____



**Terms & conditions of the Tender specifications of limited enquiry
Tender for Erection work of 33 KV Bay for M/S Rajasthan Housing Board (deposite
work) at 132 KV GSS Suwana ,Bhilwara on BSR as on 01.04.2017, under limited
enquiry Tender No TN-02/2017-18**

01 Prices: The price shown of above in G-schedule of work & rates are on RVPNL BSR as on 01.04.2017 vide RVPN/SE(Contracts-II)/xen-4/F./D-45 JAIPUR Dt-21.04.17 the contractor should be advised to quote the rates including all taxes as applicable.

02 EMD deposit: You'll have to furnish the security deposit @ 2% of the contract value in cash or by bank draft to the AO T&C RVPN Bhilwara & enclosed copy with Tender.

03 Terms of payment: The payment or running payment if required any on the basis of the bill duly verified by the in charge of work & counter signed by the Executive Engineer Bhilwara & payment released by the AO T&C RVPN Bhilwara through RTGS/NEFT for quick & safe transfer of fund.

04 Quantities: The quantity given in G schedule are only provisional & can vary depending on the side condition. The payment shall be paid on basis of various terms of actual quantity of the work done at unit rate given in cause of schedule of work & prices the actual work can be increased/decreased as per side requirement with maximum increase of 20%.

05 Completion time: You'll have to complete work on order within a period of two month for which layout has to be given by Assistant Engineer (T&C) RVPN Bhilwara.

06 Penalty: Work completion period/time of contract is essence of contract if you fail to complete the work on order within stipulated period, the nigram shall charge penalty @ 0.50% of the cost of unexecuted portion of the work per week or part their of subject to maximum 10% of total value of unexecuted portion of work contract however no penalty will be imposed if delay is due to obligation of purchaser not being fulfilled in time.

07 Contract Agreement: The contractor shall also require to execute a contract agreement on non judicial stamp paper worth rs 500/- duly signed accepted & notarized.

08 Incharge of work: The work shall be carried out under supervision of AEN (T&C) RVPN Bhilwara under control of XEN (T&C) RVPN Bhilwara.

09 Extension in completion period: Any delay due to stoppage of work by nigram will be compensated by way of extension of completion date.

10 Distribution of material: Material shall be delivered at the work site from the store of AEN (T&C) RVPN Bhilwara & site store.

11 Electricity rules: You'll carry out all the work in accordance with revised & latest provision under Indian electricity rules & Act made their under.

12 Wastages: The contractor shall have to make every effort to minimize the breakage losses & wastages of GSS material etc, supplied free of cost by nigram for construction of GSS.

The maximum ceiling for the wastage permitted is as under:-

S.No.	ITEM NAME	% WASTAGE PERMITTED (MAX.)
1.	Conductor & Earth wire	1%
2.	Insulator	1%
3.	Bolts & Nuts	No extra bolts & nuts shall be supplied 2%
4.	Hard ware & Accessories	1%
5.	M.S.Flat/M.S.Road	1%

The contractor shall maintained & submit the account of actual wastage with the MAS Account, In case wastage are more than permitted quantities then contractor shall have to compensate to nigram for excess wastage by double the issue rate of material.


13 Scope of work: This contract covers erection & construction work of 33 kv bay which include all activities as mentioned in G schedule of work & G schedule/quoted rates the quantum of work involved as per enclosed G schedule of work (copy of detailed G schedule enclosed).

14 Erection insurance: The contractor shall take suitable storage come erection insurance policy for subject work material at his own cost. The Estimated cost of Project/material for insurance purpose shall be intimated by Engineer in charge of work. The insurance policy should be submitted to this office i.e. Executive Engineer (T&C) RVPN Bhilwara for its acceptance.

16. Quality check/Inspection: Surprise check of the vendor/supplier premises can be done by quality control, inspection & monitoring section of the RVPN'S cooperate office on a short notice for which all necessary arrangement towards inspection of the RVPN'S supply/work order are to be arranged by the vendor supplier for ensuring quality as per RVPN requirement. The vendor/supplier shall also provide all requisite co-operation/assistance & facility for such quality check/inspection.

15. Responsibilities: In case of any fatal/non fatal accident occurred during the execution of work all responsibilities will be borne by contractor & RVPN, will not take any responsibility legal/financial.

16. Qualifing Requirement: The contractor have to registered in "E" category in RVPN.



**Executive Engineer(T&C)
RVPN BHLWARA**

I AGREE TO DO THE ABOVE WORKS ON _____% ABOVE/BELOW IN G-SCHEDULE AMOUNT BASED ON 2011 BSR

SIGNATURE OF CONTRACTOR