



**RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED**

(An ISO 9001:2008 Certified Company)

**OFFICE OF THE ASSISTANT ENGINEER (132 KV GSS)**

**RRVPL, NAWA (NAGOUR) RAJASTHAN**

(Tel. No. 01586-262686, E-Mail Id: [aen.132.Nawa@rvpn.co.in](mailto:aen.132.Nawa@rvpn.co.in))

**No. RRVPL /AEN /132kv /GSS /Nawa /F. /D. 31 Dated:- 27.04.2017**

To ,

All Registered contractors  
Under (T&C) Ajmer Zone

Sub:- consent for execution of Distaining & straining of Earth wire of 132 KV Phulera- nawa line on CLRC for FY 2017-18

Dear sir

Your consent is desired for execution of Distaining & straining of Earth wire of 132 KV Phulera-nawa line at 132 KV GSS RVPN Nawa for the year 2017-18 on CLRC basic as per details maintained in G schedule.

There for your requested to convey your consent within 7 Days up to 16.00 PM on dated 04/05/2017 in writing along with copy of valid registration so the case may be further process.

Encl:- G Schedule of the Straining of Earth wire

Assistant Engineer  
132 KV GSS RVPN Nawa



# **RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED**

(An ISO 9001:2008 Certified Company)

OFFICE OF THE ASSISTANT ENGINEER (132 KV GSS) RRVPNL, NAWA (NAGAU) RAJASTHAN  
No. RRVPNL /AEN /132kv /GSS /Nawa /F. /D. 30 Dated:- 27/04/2017

## **G-Schedule**

Work of distaining & straining of earth wire of 132 KV Phulera –Nawa Line

S.no	BSR Code No.	Particulars	Unit	Rate	Qty.	Amount
1		2	4	5	6	7
1	16	distaining of Earth wire: Dismantling of earth bonds ,vibration damper, & fitting in rollers, de tensioning de clipping collecting the material & depositing the same in our store and stacking.(All material shall be arranged by RVPN. All T&P shall be arranged by the contractor) One no 7/3.15 mm galvanized wire	Per KM	4105.00	5KM	20525.00
2	14	(A) straining of Galvanized steel standard wire: including laying ,joint & tensioning, clamping, clipping and fixing vibration damper and earth bound etc .(All material shall be arranged by RVPN. All T&P shall be arranged by the contractor) One no7/3.15 mm galvanized wire	Per KM	3737.00	6KM	22422.00
Total						42947.00
O/H charges on the basis of CLRC @ 63.6%						27185.451
Amount upto date include O/H charges						76977.072
Say Rs.						70132.451

Amount in words (Rs.) Seventy Thousand one Hundred thirty two Rupees.

### Note

- 1) Rate has been taken from BSR rate list as on dated 01.08.2008
- 2) Cost of Premium taken as per letter no. RVPN/SE/TLPC/XEN/TL-A4/BSR/D.2054 dt.27/08/2008

Junior Engineer  
132 KV GSS RVPN Nawa

Assistant Engineer  
132 KV GSS RVPN Nawa