

RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED
(Reg. Office: Vidyut Bhawan, Janpath, Jyoti Nagar, Jaipur-302 005)
OFFICE OF THE ASSISTANT ENGINEER (132 KV GSS)
Deedwana, Nagaur- 341303, Telephone No.01580-220016
E-mail: aen_132_deedwana@rvpn.co.in
No.RRVPNL/AEN/132 KV GSS/Deed/Estt./F. /D.32 Dated:- 22/05/2017

All Registered contractor,
under the ZCE(T&C A/Z), AJMER

- **SUB:-**Maintenance of restringing at 132kv deedwana-sujangarh line on CLRC rate contract at 132 KV GSS DEEDWANA.

In reference to subject cited above it is intimated that the work of restringing at 132 kv deedwana-sujangarh line maintenance at 132 KV GSS DEEDWANA is to be carried out on CLRC rate contract.

If you are interested to carry out the said work please give your consent within a period of 7 days from 22.05.2017 TO 29.05.2017 the issue letter otherwise it will be presumed that you are not interested to carry out the said work and work will be awarded to any other firm.

Encl:-G schedule


ASSISTANT ENGINEER (132 KV GSS)
RVPNL DEEDWANA

Copy submitted to the XEN 220 KV Gss Kuchaman City for information and necessary action


ASSISTANT ENGINEER (132 KV GSS)
RVPNL DEEDWANA

RAJASTHAN RAJYA VIYUT PRASARAN NIGAM LTD
OFFICE OF THE ASSISTANT ENGINEER (132 KV GSS) RVPN, deedwana

G' Schedule For Earth wire restringing at 132 kv deedwana-sujangarh line

S.No	Description	Unit	Rate(Rs)	Qty	Amount
1	EARTHWIRE STRINGING				
1	(A) Stringing of galvanised steel stranded wire including laying, jointing & tensioning, clamping, clipping and fixing vibration damper and earth bond etc.				
	(i) One No. 7/3.15mm galvanised wire	Km	6713.00	3.2KM	21481.60
2	(C) Restringing of Earthwire: -Dismantling of earth bond, vibration dampers, declipping & fitting in rollers, de-tensioning, holding & lowering of Earthwire, adding/removing and jointing of Earthwire, lifting into rollers and re-tensioning, jointing, clipping & fitting of vibration dampers & earthbond per route KM of the line section to be restrung. Dismantled material not re-used to be deposited in our stores & stacked.				
	(l) One No. 7/3.15mm galvanised wire	Km	6713.00	2.1KM	14097.30
	Total				35579
	As per CLRC rates contract 60% above BSR				21347
				GRAND TOTAL	56926

1 The rates for the erection works given in this G-Schedule are inclusive of all types of labour charges

2 It is certified that the basic schedule of rates for erection works as per letter No.856 Dated 25-06-2015 by SE (TLPC), Jaipur.

Rjesh
 JEN(M)

[Signature]
 ASSISTANT ENGINEER (132 KV GSS)
 RVPN, Deedwana