

**RAJASTHAN RAJYA VIYUT PRASARAN NIGAM LTD**  
**OFFICE OF THE ASSISTANT ENGINEER (132 KV GSS) RVPN, deedwana**

**G' Schedule For Earth wire restringing at 132 kv deedwana-sujangarh line**

S.No	Description	Unit	Rate(Rs)	Qty	Amount
1	<b>EARTHWIRE STRINGING</b>				
1	(A) Stringing of galvanised steel stranded wire including laying, jointing & tensioning, clamping, clipping and fixing vibration damper and earth bond etc.				
	(i) One No. 7/3.15mm galvanised wire	Km.	6713.00	3.2KM	21481.60
2	(C) Restringing of Earthwire: -Dismantling of earth bond, vibration dampers, declipping & fitting in rollers, de-tensioning, holding & lowering of Earthwire, adding/removing and jointing of Earthwire, lifting into rollers and re-tensioning, jointing, clipping & fitting of vibration dampers & earthbond per route KM of the line section to be restrung. Dismantled material not re-used to be deposited in our stores & stacked.				
	(I) One No. 7/3.15mm galvanised wire	Km.	6713.00	2.1KM	14097.30
	<b>Total</b>				<b>35579</b>
	<b>As per CLRC rates contract 60% above BSR</b>				<b>21347</b>
			<b>GRAND TOTAL</b>		<b>56926</b>

- 1 The rates for the erection works given in this G-Schedule are inclusive of all types of labour charges  
2 It is certified that the basic schedule of rates for erection works as per letter No.856 Dated 25-06-2015 by SE (TLPC), Jaipur.



**ASSISTANT ENGINEER (132 KV GSS)**  
**RVPN, Deedwana**