

# RAJASTHAN RAJYA VIDHYUT PRASARAN NIGAM LIMITED

VIDHYUT BHAWAN, JANPATH, JYOTI NAGAR, JAIPUR

**(An ISO 9001:2008 Certified Company)**

Office of The Assistant Engineer (132 KV GSS) RVPN, Kumawas (Jhunjhunu)

TEL No. 01594-271210, Mob. 09462511930, Email- [aen.132.kumawas@rvpn.co.in](mailto:aen.132.kumawas@rvpn.co.in)


No: RVPNL/AEN/132 KV GSS/KWS/Estt/F: 24 /D: 64 / Dated 15.06.2017

To  
All Contractors,  
Ajmer Zone

**Sub:** Acceptance for execution of Channel and equipment painting at 132kV GSS RVPN Kumawas on CLRC basis.


On the above cited subject, kindly find enclosed herewith the G-Schedule for execution of Channel and equipment painting work at 132kV GSS Kumawas as per terms and conditions given herein. The acceptance for execution of Channel and equipment painting works should be handed over personally at above address or be sent per registered post to this office up to 18:00 hrs. on dated 27-06-2017.

Enclosed :- 'G' Schedule

  
Assistant Engineer  
(132 KV GSS) RVPNL  
Kumawas (Jhunjhunu)

Copy submitted to the following for information and necessary action please:-

1. The Superintending Engineer (T&C), RVPN, Babai
2. The Executive Engineer (220kV GSS), RVPN, Jhunjhunu
3. The Accounts Officer (T&C), RVPN, Babai
4. The Feeder Manager (T&C), RVPN, Sikar
5. Notice Board.


  
Assistant Engineer  
(132 KV GSS) RVPNL  
Kumawas (Jhunjhunu)

**(A) G-Schedule for Painting of Channel Painting work at 132 KV GSS RVPN Kumawas**

S.No.	Description of work	Unit	Total area required to be painted(Square meter)	Cost per Square meter (RS.)	Total Cost(Rs.)
1.	<p><b>Painting of Old Painted Channel :-</b> Alluminium Painting of old painted channel at 132 KV GSS RVPNL Kumawas including paint &amp; painting brush, emery paper, cloth &amp; solvent etc. The surface shall be first rubbed with wire brush/emery paper and thereafter wiped with cloth to remove rust and dust or any other deposits on installed M.S. Channel. Two coats of aluminum paint shall be applied. Each subsequent coat shall be applied after the previous coat has fully dried up. The paints used shall be out of the following recognized manufactures, namely Asian/Nerolac/Berger/Jenson Nicholson</p>	Sq. Mtr.	65.61 Sq.Mtr.(Approx.)	24 Per Sq. Mtr.	Rs. 1574.64
			<b>TOTAL AMOUNT</b>		1574.64
<b>Add 60% premium of total amount</b>					944.78
<b>(A) GRAND TOTAL AMOUNT</b>					2519.42

**(B) G-Schedule for Painting of Transformer & Equipments work at 132 KV GSS RVPN  
Kumawas**


S.No.	Description of work	Unit	Total area required to be painted(Sq uare meter)	Cost per Square meter (RS.)	Total Cost(Rs.)
1.	<b>Painting of Sub Station Equipment:-</b> Enamel Painting on Sub Station equipment including supply of paint and spray painting set, emery paper, cloth & solvent etc. at 132 KV GSS, Kumawas by cleaning surface thoroughly with soda/caustic solution to clean oily surface & thereafter, washing with water. Thereafter two coats of smoke gray synthetic enamel paint shall be applied by spray method. Each subsequent coat shall be applied after the previous coat has fully dried up. The paints used shall be out of the following recognized manufactures, namely Asian/ Nerolac/Berger/Jenson Nicholson.	Sq. Mtr.	408 Sq.Mtr.(Approx.)	25 Per Sq. Mtr.	Rs. 10200.00
			<b>TOTAL AMOUNT</b>		10200.00
			Add 60% premium of total amount		6120.00
			<b>(B)GRAND TOTAL AMOUNT (R/Off)</b>		16320.00
			<b>GRAND TOTAL AMOUNT OF(A+B) =(2519.42+16320)</b>		<b>18839.42</b>
			<b>GRAND TOTAL AMOUNT OF(A+B) (R/OFF)</b> <b>(Rs. Eighteen thousand Eight hundred Thirty Nine Only)</b>		<b>18839.00</b>



**ASSISTANT ENGINEER  
132 KV GSS RVPN  
KUMAWAS**

Details of the Equipment/channel painting requirement is here by submitted as below:-

S.No.	Name of equipment	Quantity	Area in square meter
1.	132/33 KV, 20/25 MVA Tr. No. 1	01	360.00
2.	132 KV Current Transformer	04	9.00
3.	33 KV Current Transformer	30	39.00
4.	MS Channel		65.61
			Total= 473.61



**ASSISTANT ENGINEER**  
**132 KV GSS RVPN**  
**KUMAWAS**