


“G” Schedule


Name of work: - Painting of Fire Fighting System pipes at 400 kV GSS Bikaner

Ref: - 1. BSR No. RVPN / SE/(SSPC)/ XEN(TK)/ BSR/ A1/D. 21 Dated: 04.04.2011.

2. CLRC No. RVPN/SE/SSPC/TK/A.1/TN-2975/ CLRC/D.501 Dated 24.05.2013.

S. No.	BSR Code No.	Description	Unit	Unit Rate in Rs.	Qty.	Amount	CLRC Rate Above 60 %	Net Amount as per CLRC
1.	2.2	PAINING OF OLD PAINTED STEEL STRUCTURES: Painting of old painted steel structures at the GSS including paint and painting brush, emery paper, cloth and solvents, etc. The surface shall be first cleaned with wire brush / emery paper and thereafter wiped with cloth to remove rust and dust or any other deposits on erected M.S. steel structure & beam. One coat of red oxide pain shall be applied after carrying out cleaning and allowed to dry. Thereafter, two coats of aluminium paint shall be applied. Each subsequent coat shall be applied only after the previous coat has dried up. The paints used shall be from any of the following recognized manufacturers, namely Asian / Nerolac / Berger / Jenson Nicholson.	Sq. Meter	24.00	1244.788	29874.91	17924.95	47799.85
Grand Total								47799.85


 Assistant Engineer (400 KV GSS)
 RRVPL, Bikaner


 15/4/17