



RVPN
An ISO 9001:2000
Certified Company

RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED

(Reg. Office: Vidyut Bhawan, Janpath, Jyoti Nagar, Jaipur-05)

OFFICE OF THE EXECUTIVE ENGINEER

220 KV GSS, SURATGARH – 335 804 (RAJASTHAN)

Telephone No.01509 – 220245

E-mail: xen_220_suratgarh@rvpn.co.in

Ref No. RRVPNL/XEN/SOG/Tech/Tender/D - 300 Dated: 08.09.2017

LIMITED TENDER NO. 01... (2017-2018), DUE ON 15.09.2017..

Name of the Work – Replacement of damaged earth wire of 132 KV S/C Sardarshahar-Rajiasar line under 220 KV GSS Suratgarh Division.

M/s Bhawani Cont. Co.

..... Ward No. 09, Anoopgarh

..... Srijanga Nagar.....

M/s Jagdish Chaudhary
Thakri, Raisiyahwagar
Srijanga Nagar

M/s Mahalaxmi Enterprises Kirti
Stambh Bidasar House
Bikaner

01. Limited Tender is invited for carrying out the work as per Annexure-1 & 'G' Schedule.
02. The tender must be submitted in sealed envelopes superscripted clearly with the "Name of work" and tender number duly addressed to **Executive Engineer, 220 KV Grid Sub Station, RRVPNL, Suratgarh – 335 804, (Rajasthan)** and shall be deposit with the concern authority before due date.
03. The **tender submission due date is 15.09.2017 (after 07 days from publication of NIT date) till 05.00 pm** & will be **opened on next working day of due date i.e. 18.09.2017 at 11.00 am** in the chamber of XEN 220 KV GSS RVPN Suratgarh in the presence of the tenderers if any.
04. Any over righting and cutting on tender should not be accepted and the same will be rejected
05. Tenders uncompleted in any respect will not be considered.
06. All addition and alterations in the tender submitted must be clearly initiated. The rates should also be quote rates both in words and figures, wherever there is any difference between rates in figure and word the lower rates is accepted
07. Tender received late on any a/c shall not be considered.
08. Tender offer will be valid for 90 days from the date of opening of tender
09. All the enclosed documents should be stamped & signed by the tendering firm
10. Tenderer is not allowed to submit the conditional tender and all conditional tender shall be rejected
11. Tenderer should comply all the items mentioned in tender notice, general condition of tender, general condition of contract.
12. The undersigned does not bind him-self to accept the lowest tender or any tender and reserve the right to reject any or all of the tenders without assigning any reason thereof.
13. Payment Terms- 90% Payment will be made within a month after completion of work & on presentation of bill in triplicate and balance 10% after 06 months from the date of satisfactory completion of the work.
14. The quantity of work/ material may be increased / decreased by 10% as per requirement.
15. The tenderer is bind to complete the work in the stippled time frame given in the contract documents.
16. Tenderer should give the details of taxes, service tax or any other charges if livable, after opening of tender it will not be considered.
17. As this work is petty work & being limited tender, hence no tender cost is required. The EMD by the 1st lowest firm @ 2% will be deposited after opening of the tender.

Encl:- Annex-I & 'G' Schedule.

(Er. J K Chhabra)

EXECUTIVE ENGINEER (220 KV GSS)
RRVPNL, Suratgarh

Copy submitted/ forwarded to the following for kind information & n/s please:-

- (i) The Superintending Engineer (T&C) RRVPNL, Hanumangarh.
- (ii) The Feeder Manager (T&C) RRVPNL, Bikaner with the request to kindly upload above limited tender on RVPN website.
- (iii) The AO (T&C) RVPN Hanumangarh. (Please depute your representative on the time of opening the tender documents).
- (iv) Notice Board.

EXECUTIVE ENGINEER (220 KV GSS)
RRVPNL, Suratgarh

Annexure - I


This schedule is for Replacement of damaged earth wire of 132 KV S/C Sardarshahar-Rajiasar line under 220 KV GSS Suratgarh Division.

1.0 Job description:

Sl. No.	Description of Job & Work	Unit	Qty. in Km.	Rate in INR	Total Amount in INR
1.	(C) Restrunging of Earthwire: between line location no. 432 (B) to 443 (B) of 132 KV Sardarshahar-Rajiasar line under 220 KV GSS Suratgarh. Dismantling of earth bond, vibration dampers, declipping & fitting in rollers. De-tensioning, holding & lowering of Earthwire, adding removing and jointing of Earthwire, lifting into rollers and re-tensioning. jointing, clipping & fitting of vibration dampers & earthbond per route KM of the line section to be restrung. Dismantled material not used to be deposited in our stores & stacked. (i) One No. 7/3.15mm galvanised wire	Km.	04		


2.0 Terms of work: -

- 2.1 the contractor should have valid GSTIN No. and shall also have necessary registration with concerned Govt. Deptt. Wherever required under the law.
- 2.2 The contractor shall ensure the use of safety devices, which are to be provided the contractor and shall take precautions as per norms.
- 2.3 the contractor shall follow a safe method of working so that there is no any damage to Nigam's material as well as no injury to any of his workers.
- 2.4 The contractor shall be fully responsible for the safety of workers, and RVPN will not be responsible for any type of accident minor or fatal to any person at work-site.
- 2.5 The contractor should have capability of providing required labor under emergent circumstance at short notice.
- 2.6 All the work men provided by the contractor shall be insured for the accidents by the contractor.
- 2.7 The contractor should have responsible to cover all risk arising due to act of omission of his employees which results in loss/injury to the contractor/ his employees/ RVPN or to the third parties if any.
- 2.8 The work must be completed within 90 days from the date of issue of the work order.


Executive Engineer
220 KV GSS, RRVPNL, Suratgarh


Asstt. Engineer (Maint)
220 KV, GSS, RRVPN
Suratgarh


JEN (M) 220 KV GSS
RRVPNL SURATGARH


AO (T&C)
RVPNL

OFFICE OF THE EXECUTIVE ENGINEER (220 KV GSS)
RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LTD.
SURATGARH


'G' Schedule for Replacement of damaged earth wire of 132 KV S/C Sardarshahar-Rajiasar line under 220 KV GSS Suratgarh Division .

Sr. No.	BSR Item No.	Description	Unit	Rate	Qty.	Amount
1	17	(C) Restrunging of Earthwire: between line location no. 432 (B) to 443 (B) of 132 KV Sardarshahar- Rajiasar line under 220 KV GSS Suratgarh. Dismantling of earth bond, vibration dampers, declipping & fitting in rollers. de-tensioning, holding & lowering of Earthwire, adding removing and jointing of Earthwire, lifting into rollers and re-tensioning. jointing, clipping & fitting of vibration dampers & earthbond per route KM of the line section to be restrung. Dismantled material not ne-used to be deposited in our stores & stacked.				
(i)	(a)	(i) One No. 7/3.15mm galvanised wire	Kms.	6713	4	26852
TOTAL						26852
Net Total in Rs.						26852.00
(In words Rs. Twenty Six Thousand Eight Hundred and Fifty Two only)						


Note:-

1. The BSR rates for the EHV lines on labor contract basiseffective from 01.04.2015

2. Above rates are inclusive of all types of charges) taxes with GST.


Assistant Engineer (M)
220 KV GSS RVPN SURATGARH


JEN (M) 220 KV GSS
RRV/NL SURATGARH


Executive Engineer
220 KV GSS RVPN SURATGARH

By quote my rates as% Above / Below of the rates as mentioned above.

Signature of Contractor with Seal
Name of Contractor/Firm
Contact No.