



## RAJASTHAN RAJYA VIDHYUT PRASARAN NIGAM LTD

An ISO 9001 : 2000 Certified Company

OFFICE OF THE ASSISTANT ENGINEER (132 KV GSS), CHB, Jodhpur

RVPN/AEN/132 KV/GSS/CHB/JU/F. /S.ESTT/CASH/TECH.

D.No Dt 22/05/2017

To,

1. M/s Hitech Engineers & Contractor, Shiv Road, Jaisalmer
  2. M/s Angira Engineering works Khandela Road Srimadhapur Sikar
  3. M/s Guru Kripa Enterprises pahad ganj behind W/W Lal Sagar Road Jodhpur
  4. M/s H.S. Engineering, Majdoor Para Gadisar gate, Jaisalmer
  5. M/s Good Luck Enterprises A-14, RIICO Housing Colony, Ajmer Road, Beawar
  6. M/s Mahadev Eng. Works ,Plot No.30, Tandion Ki Dhani, Main Salawas Road, Sanghariya, Jodhpur
  7. M/s Ridhi Sidhi Construction, Jaisalmer .170, Sadulpara VPO- Mulana, Tehsil- Fatehgarh Distt.- Jaisalmer
  8. M/s A.G. Enterprises 18 Clock Tower, Alwar
  9. M/s Amar Bhaw Corporation A-14 Kamla Nehru Nagar, Ext-2 Opp-Somani College, Jodhpur
  10. M/s Shree Techno Services, House No.188 ,Shiv Road, Ratanada, Jodhpur
- And All

**Subject :** Painting of Sub Station steel structure at 132 KV GSS CHB Jodhpur.

The Painting of Sub Station steel structure at 132 KV GSS CHB Jodhpur as per 'G' schedule. The above work is to be done as per CLRC rates/rules/guide lines of RVPN applicable for the year 2017-18.

So if your firm is interested to carry out the work, please give your acceptance within 10 days otherwise it will be presumed that you are not interested to take up the work.

Encl: 'G' Schedule of work

  
ASSISTANT ENGINEER, 132 KV GSS,  
RRVPL, CHB, JODHPUR.

**G- SCHEDULE FOR PAINTING OF STRUCTURES AT 132KV GSS CHB, JODHPUR**

S.No	Description	Unit	Qty.	Rate	Amount
1	2	3	4	5	6
	<b>PAINTING OF STRUCTURE &amp; EQUIPMENTS</b>				
A	<p><b><u>PAINTING OF OLD PAINTED STEEL STRUCTURES</u></b></p> <p>Aluminium painting of old painted steel structures of the GSS including supply of paint and painting brush, emery paper , cloth &amp; solvent etc. The surface shall be first cleaned with wire brush/emery paper and there after wiped with cloth to remove rust and dust or any other deposit on erected MS steel structure. Two coats of aluminium paint shall be applied. Each subsequent coat shall be applied only after the previous coat has dried up. The paint used shall be from any of the following recognized manufacturers namely Asian/Nerolac/Berger/Jenson Nicholson</p>	SQM	2682.20	24.00	64372.80
	<b>NOTE: FOR YEAR 2017-18, CLRC RATE IS 60% ABOVE B.S.R 01.01.2011</b>			(+)	38623.68
				<b>GRAND TOTAL</b>	<b>102996.48</b>

  
**ASSISTANT ENGINEER 132 KV GSS**  
**RRVNL CHB JODHPUR**