

RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED

(Reg. Office: Vidyut Bhawan, Janpath, Jyoti Nagar, Jaipur-05)

OFFICE OF THE EXECUTIVE ENGINEER

220 KV GSS, SURATGARH – 335 804 (RAJASTHAN)

Telephone No.01509 – 220245

E-mail: xen_220_suratgarh@rvpn.co.in

Ref No. RRVPL/XEN/SOG/Tech/Tender/D - 845 Dated: 13.2.17

LIMITED TENDER NO 08 (2016-2017), DUE ON 20.02.2017

Name of the Work – 220/132 KV Transformers Painting work at 220 KV GSS Suratgarh.

M/s

01. Limited Tender is invited for carrying out the work as per Annexure-1 & 'G' Schedule.
02. The tender must be submitted in sealed envelopes superscripted clearly with the "Name of work" and tender number duly addressed to **Executive Engineer, 220 KV Grid Sub Station, RRVPL, Suratgarh – 335 804, (Rajasthan)** and shall be deposit with the concern authority before due date. *i.e. 20.02.2017 3.00 pm.*
03. The tender will be opened at **4.00 pm on Dt. 20.02.2017** in the presence of the tenderers if any.
04. Any over righting and cutting on tender should not be accepted and the same will be rejected
05. Tenders uncompleted in any respect will not be considered.
06. All addition and alterations in the tender submitted must be clearly initiated. The rates should also be quote rates both in words and figures, wherever there is any difference between rates in figure and word the lower rates is accepted
07. Tender received late on any a/c shall not be considered.
08. Tender offer will be valid for 90 days from the date of opening of tender
09. All the enclosed documents should be stamped & signed by the tendering firm
10. Tenderer is not allowed to submit the conditional tender and all conditional tender shall be rejected
11. Tenderer should comply all the items mentioned in tender notice, general condition of tender, general condition of contract.
12. The undersigned does not bind him-self to accept the lowest tender or any tender and reserve the right to reject any or all of the tenders without assigning any reason thereof.
13. Payment Terms- 90% Payment will be made within a month after completion of work & on presentation of bill in triplicate and balance 10% after 06 months from the date of satisfactory completion of the work.
14. The quantity of work/ material may be increased / decreased by 10% as per requirement.
15. The tenderer is bind to complete the work in the stippled time frame given in the contract documents.
16. Tenderer should give the details of taxes, service tax or any other charges if livable. after opening of tender it will not be considered.
17. As this work is petty work & being limited tender, hence no tender cost is required. The EMD by the 1st lowest firm @ 2% will be deposited after opening of the tender.

Encl:- Annex-I & 'G' Schedule.

(Er. J K Chhabra)
EXECUTIVE ENGINEER (220 KV GSS)
RRVPL, Suratgarh

Copy submitted/ forwarded to the following for kind information & n/s please:-

- (i) The Superintending Engineer (T&C) RRVPL, Hanumangarh.
- (ii) The Feeder Manager (T&C) RRVPL, Bikaner with the request to kindly upload above limited tender on RVPN website.
- (iii) The AO (T&C) RVPN Hanumangarh. (Please depute your representative on 20.02.2017 for opening the tender documents)
- (iv) Notice Board

EXECUTIVE ENGINEER (220 KV GSS)
RRVPL, Suratgarh

Annexure - I

This schedule is for 220/132 KV Transformers Painting work at 220 KV GSS Suratgarh.

1.0 Job description:

Sl. No.	Description of Job & Work	Unit	Qty. In Meter 2	Remarks
1.	Enamel painting on 02 Nos. 220/132 KV power transformers and other equipment's including supply of paint and spray painting set, emery paper, cloth & solvents. etc. at GSS by cleaning surface thoroughly with soda / caustic solution to clean oily surface and thereafter washing with water. Thereafter, two coats of smoke gray synthetic enamel paint shall be applied by spray method. Each subsequent coat shall be applied after the previous coat has fully dried up. The paints used shall be from any of the following recognized manufacturers, namely Asian/ Nerolac/ Berger/Johnson Nicholson. In case of surface area of radiators, those fins will only be considered which are actually feasible and approachable for painting by spray or by brush.	Meter ²	1126	

2.0 Terms of work: -

- 2.1 the contractor should have valid electrical license and shall also have necessary registration with concerned Govt. Deptt. Wherever required under the law. ²
- 2.2 The contractor shall ensure the use of safety devices, which are to be provided the contractor and shall take precautions as per norms.
- 2.3 the contractor shall follow a safe method of working so that there is no any damage to Nigam's material as well as no injury to any of his workers.
- 2.4 The contractor shall be fully responsible for the safety of workers, and RVPN will not be responsible for any type of accident minor or fatal to any person at work-site.
- 2.5 The contractor should have capability of providing required labor under emergent circumstance at short notice.
- 2.6 All the work men provided by the contractor shall be insured for the accidents by the contractor.
- 2.7 The contractor should have responsible to cover all risk arising due to act of omission of his employees which results in loss/injury to the contractor/ his employees/ RVPN or to the third parties if any.
- 2.8 The work must be completed within 90 days from the date of issue of the work order.




Executive Engineer
220 KV GSS, RRVNPL, Suratgarh

OFFICE OF THE EXECUTIVE ENGINEER (220 KV GSS)
RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LTD.
SURATGARH

**'G' Schedule for Painting work of 02 Nos. 220/132 KV Power Transformers
installed at 220 KV GSS SURATGARH.**

Sr. No.	BSR Code No.	Description	Unit	Rate	Qty.	Amount
1	2	STRUCTURE PAINTING WORK:-				
i)	2.3	PAINTING OF TRANSFORMERS & EQUIPMENTS:				
		Enamel painting on power transformers and other equipments including supply of paint and spray painting set, emery paper, cloth & solvents, etc. at GSS by cleaning surface thoroughly with soda / caustic solution to clean oily surface and thereafter washing with water. Thereafter, two coats of smoke gray synthetic enamel paint shall be applied by spray method. Each subsequent coat shall be applied after the previous coat has fully dried up. The paints used shall be from any of the following recognized manufacturers, namely Asian/ Nerolac/ Berger/Johnson Nicholson. In case of surface area of radiators, those fins will only be considered which are actually feasible and approachable for painting by spray or by brush.				
			Meter ²	25	1126	28150
		TOTAL				28150
		Net Total in Rs.				28150.00
(In words Rs. Twenty Eight Thousand One Hundred Fifty only)						

Note:- 1. The rates for the above works are the BSR for Repair & Maintenance works of EHV Lines & GSS -2011 of RVPN


Assistant Engineer (M)
220 KV GSS RVPN SURATGARH


Executive Engineer
220 KV GSS RVPN SURATGARH

By quote my rates as% Above / Below of the rates as mentioned above

Signature of Contractor with Seal
Name of Contractor/Firm
Contact No.