

**G-Schedule for painting of old steel painted structure at 132 KV GSS, Salasar for the year 2016-17**

No.	Description of work	Unit	Rate as per BSR in Rs.	Area in Sq. Mtr.	Total Amount in Rs.
1.	Aluminum painting of old painted steel structure at the GSS including the supply of paint and painting brush, emery paper, cloths and solvents etc. the surface shall be first cleaned with wire brush/ emery paper and thereafter wiped with cloth to remove rust and dust or any other deposit on erected M.S. steel structure. Two coats of aluminum shall be applied only after the previous coat has dried up. The paint used shall be from any of the following recognized manufacturer namely Asian/ Nerolac/Berger/Johnson Nicolson	Sq. Mtr.	24.00	729	17496.00
2.	Enamel painting of power transformer and other equipment's including supply of paint and spray painting set, emery paper, cloth and solvents etc. at GSS by cleaning surface thoroughly with soda/caustic solution to clean oily surface and thereafter washing with water. Thereafter two coats of smoke gray synthetic enamel paint shall be applied by spray method. Each subsequent coat shall be applied after the previous coat has fully dried up. The paints used shall be from any of the following recognized manufacturer namely Asian/Nerolac/Berger/Johnson Nicholson. In case of surface area of radiators those fins will only be considered which are actually feasible and approachable for painting by spray or by brush.	Sq. Mtr.	25.00	650	16250.00
3.	Enamel painting on Marshalling Kiosks including supply of paint and spray painting set, emery paper, cloth and solvents etc. at GSS by cleaning surface thoroughly with soda/caustic solution to clean oily surface and thereafter washing with water. Thereafter two coats of smoke gray synthetic enamel paint shall be applied by spray method. Each subsequent coat shall be applied after the previous coat has fully dried up. The paints used shall be from any of the following recognized manufacturer namely Asian/Nerolac/Berger/Johnson Nicholson.	Sq. Mtr.	25.00	50	1250.00
	<b>Total</b>	<b>Sq. Mtr.</b>	<b>25.00</b>	<b>1429</b>	<b>34996.00</b>

Total Painting Area = 1429 Sq.Mtr.


Total Amount (BSR) = 34996.00


CLRC rate is 60% above BSR Total amount (CLRC) = 20997.60

Grand Total  
SayRs. 55993.60  
Rs. 55994.00

(Rs. Fifty Five Thousand Nine Hundred Ninety Four only)

  
**Junior Engineer (M)**  
 132KV GSS, Salasar

  
**Assistant Engineer**  
 132 KV GSS, Salasar

  
**Executive Engineer**  
 220 KV GSS, Sujangarh