



RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LIMITED

(AN ISO 9001:2008 CERTIFIED COMPANY)

Corporate Identity Number (CIN) : L40109RJ2000SGC016485

REGD. OFFICE VIDYUT BHAWAN, JANPATH, JYOTI NAGAR, JAIPUR-302005

OFFICE OF THE SUPERINTENDING ENGINEER (T&C), RVPN, JODHPUR.

NO. RVPN /SE/ T&C / Ju. /S. Purchase / F.

/ D.

Dt.

2135
11/9/17

TO,


**All Registered Contractors of,
T&C RVPN Jodhpur Zone,**

Subject: - Patrolling of 400 kV lines emanating from 400 kV GSS, Jodhpur on CLRC rate on BSR 2011 for financial year 2017-2018.

On the above cited subject it is to bring to your kind notice that Patrolling of 400 kV lines emanating from 400 kV GSS, Jodhpur on BSR 2011 for financial year 2017-2018 is to be done on CLRC rate (as per "G" schedule enclosed) on the terms & conditions of CLRC rate contract as approved by RVPN.

If you are interested for carrying out this work on CLRC rate (i.e. 60% above as per "G" schedule), please send your consent/acceptance within 10 days from the date of dispatch of this letter.

Encl:- "G" Schedule.


Superintending Engineer (T&C),
RVPNL, Jodhpur

RAJASTHAN RAJYA VIDHYUT PRASARAN NIGAM LIMITED

"G" Schedule of line patrolling/tree cutting of 400 KV lines emanating from 400KV GSS, Surapura, Jodhpur (2017-18)

Code No.	Description	Unit	Rate	Quantity	Amount(Rs.)
7	Maintenance of EHV lines:-				
7.1	Routine patrolling of lines and report submission:- Routine patrolling /inspection of 400/220/132Kv lines including detailed inspection with binocular(to be arranged by contractor).The inspection/checking is to be done as per directions/instructions in the erstwhile RVPN maintenance manual for transmission lines which includes checking of the followings:-(a)Tower&Structures,their foundations,revetments,earthing,tower members,nuts&bolts etc.(b)Condition of earthwire and their accessories/hardware.(c)Horizontal&verticle clearances of conductors.Areport of the patrolling is to be prepared in the performa prescribed in the manual/documents. Transportation & halting arrangement as required shall be made by the contractor.	Per Route KM	161	320	51520.00
7.6	Cutting of trees including cutting of trunks,braches and removal of stamps:-Cutting of trees including cutting of trunks,braches and removal of stamps ands roots,refilling,compaction of backfilling and stacking of servicable material by manual means with all lifts				
	(a)Girth upto 300mm	Each	36	185	6660.00
	(b)Girth above 300mm to 600mm	Each	77	109	8393.00
	(c)Girth above 600mm to 900mm	Each	132	47	6204.00
				Total(Rs.)	72777.00
				Add premium at 60%	43666.20
				G. Total	116443.20

Rs. One lac sixteen Thousand four Hundred & forty three Only

The above rates are inclusive of all types of applicable taxes

Junior Engineer

Assistant Engineer

Executive Engineer
 EXECUTIVE ENGINEER
 400 K.V. G.S. SURPURA LTD.
 JODHPUR (RAJ)