


OFFICE OF THE Executive Engineer (220 KV GSS), RVPN, BHAWAD

"H" Schedule

S.No.	Particular		Rate	Amount
01.	<p>Complete repairing of 220 KV D/C Bhawad-Bhopalgarh (Ckt-IIInd) between location No. 60 to 62 damaged on 21.08.2017</p> <ol style="list-style-type: none"> 1) Including dehoisting & restringing of conductor from Tension type loc no 60 to suspension type location No. 62 by providing 2-3 nos compressor joints 2) re-sagging of conductor at Loc No. 60 (Angle Tower) and restringing including armoring / clipping, vibration dampers, arcing horns & jumpering of R Phase etc. 3) Changing of 06 Nos disc insulators of Tension tower loc no 60. (Y Phase both side 03 Nos discs) 4) Changing of 01 no disc insulator of R phase Tension tower loc no 60 . 5) Changing of 02 nos disc insulators B Phase Tension tower loc no 60. 6) Rehoisting of suspension insulators at Loc. No. 61 <p>(All Material will be provided by RVPN & all T&P shall be provided by contractor.)</p>	01 job		



(Signature of contractor)

AEN
 AEN 220KV
 GSS, RVPN,
 Bhawad

XEN 220 KV
 GSS RVPN
 Bhawad