



OFFICE OF ASSISTANT ENGINEER (132 KV GSS)
RAJASTHAN RAJYA VIDYUT PRASARAN NIGAM LTD., PUGAL ROAD
(An ISO 9001-2008 Certified Company)

No.RRVPNL/AEN/132KV GSS/PRD/Estt./F-/D. 122 Dated:-24/08/217

To, All Registered Contractors
RVPN, Jodhpur Zone.

Sub: - Regarding consent for painting work of steel structures & equipment's at 132KV GSS Pugal-Road as per G-schedule on CLRC approved rates.

Dear Sir,

On the above cited subject it is to inform that the Painting work of steel (Black) structure & equipment's at 132KV GSS,Pugal-Road is to be carried out at 132KV GSS RRVPNL Pugal-Road on contract basis for the year 2017-18 on CLRC rates .

If your firm is interested to carry out the work as per G-schedule enclosed herewith on CLRC contract basis then please give your acceptance/consent for above said work on or before 01/09/2017.If your acceptance till aforesaid time frame is not received In this office, it will be under stood that you are not interested in doing this work.

Encl:-G-Schedule of Painting Work

Assistant Engineer
132KV GSS,RVPNL,
Pugal Road

Copy forwarded to the following for information & necessary action please:-

1. The Superintending Engineer(T&C),RVPN,Bikaner
2. The Executive Engineer (220KV GSS), RVPN, Bikaner.
3. The Account Officer (T&C).RVPN, Bikaner.
4. The Feeder Manager (T&C), RVPN, Bikaner for uploading on RVPN Website.


Assistant Engineer
132KV GSS,RVPNL,
Pugal Road


Im
fura
25/01/17


"G" Schedule

Name of work: - Painting of structure & equipments at 132 KV GSS RVPNL Pugal Road

S. No.	BSR Code No.	Description	Unit	Unit Rate in Rs.	Qty.	Amount
1.	2.1	PAINTING OF UNPAINTED STEEL STRUCTURES: Aluminium painting of unpainted steel structures at the GSS including paint and painting brush, emery paper, cloth and solvents, etc. The surface shall be first cleaned with wire brush / emery paper and thereafter wiped with cloth to remove rust and dust or any other deposits on erected M.S. steel structure & beam. One coat of red oxide pain shall be applied after carrying out cleaning and allowed to dry. Thereafter, two coats of aluminium paint shall be applied. Each subsequent coat shall be applied only after the previous coat has dried up. The paints used shall be from any of the following recognized manufacturers, namely Asian / Nerolac / Berger / Jenson Nicholson.	Sq. Meter	31.00	2477.12	76790.72
2.	2.2	PAINTING OF OLD PAINTED STEEL STRUCTURES: Aluminium painting of old painted steel structures at the GSS including supply of paint and painting brush, emery paper, cloth & solvents, etc. The surface shall be first cleaned with wire brush / emery paper and thereafter wiped with cloth to remove rust and dust or any other deposits on erected M.S. steel structures. Two coats of aluminium paint shall be applied. Each subsequent coat shall be applied only after the previous coat has dried up. The paints used shall be from any of the following recognized manufacturers, namely Asian / Nerolac / Berger / Jenson Nicholson.	Sq. Meter	24.00	0	0
3.	2.3	PAINTING OF TANSFORMERS & EQUIPMENTS: Enamel painting on power transformers and other equipments including supply of paint and spray painting set, emery paper, cloth & solvents etc. at GSS by cleaning surface thoroughly with soda / caustic solution to clean oily surface and thereafter washing with water. Thereafter two coats of smoke gray synthetic enamel paint shall be applied by spray method. Each subsequent coat shall be applied after the previous coat has fully dried up. The paints used shall be from any of the following recognized manufacturers, namely Asian / Nerolac / Berger / Jenson Nicholson. In case of surface area of radiators, those fins will only be considered which are actually feasible and approachable for painting by spray or by brush.	Sq. Meter	25.00	952.52	23813.00
			Total (Rs.)			100603.72
Rs. One Lac Sixty Thousand Nine Hundred Sixty five & Ninty five Paisa only.						
The above G-Schedule has been prepared as per BSR 2011 applicable from 01/01/2011 & as per order No.RVPN/CE(Contracts)/SE(C-II)/Xen-4/D.136 Dt.04.08.2017 and work to be completed up to 31/10/2017			Above 60%			60362.23
			Grand Total (Rs.)			


Junior Engineer (M)
132 KV GSS RVPNL
Pugal -Road


Executive Engineer
226 KV GSS RVPNL, Bikaner


Assistant Engineer
132 KV GSS RVPNL
Pugal -Road