

JPR5-511

**JAIPUR VIDYUT VITRAN NIGAM LIMITED**  
**OFFICE OF THE CHIEF ENGINEER (COMMERCIAL)**

NO.JPD/CE(C)/C-I/F.4(211)Pt.V/D.2525

Jaipur, Dated - 17.10.08

**ORDER**

**Sub : Installation of 11 KV Ring Main Unit(RMU)/Ring Main Switch Fuse Unit for termination of 11 KV underground service lines in the premises of prospective HT consumer under all categories in Jaipur City.**

On the subject cited above, an order No. 2036 dt. 11.08.08 (JPR5-490) was issued for providing "Ring Main Unit"(RMU) for termination of 11KV underground service lines in the premises of prospective H.T. Consumers under all categories in Jaipur City by such consumers.

The matter was again discussed & as decided, following instructions are issued in partial modification of the order No.JPR5-490 dt. 11.08.08.

1. For feeders on which the work of under grounding of cable has been taken up or is proposed to be taken up including the list of feeders furnished by the J.D.A :-
  - (I) The (RMU) "Ring Main Unit" as per the requirement/design of Jaipur Discom should be installed for H.T. supply connections & Building Complexes having contract demand/designed demand (For building complexes) above 500KVA by prospective consumers.
  - (II) Prospective H.T. consumers of Building Complexes (s) having contract demand/designed demand (For building Complexes) up to 500KVA are allowed to provide "Ring Main Switch Fuse Unit" instead of "Ring Main Unit".
2. The Old system of releasing connection shall continue as hitherto where HT grounding works for feeders has not been taken up or is proposed to be taken up.

*mm*  
17.10.2008  
( N.M.Sareen )

Chief Engineer(Comml.)

*6/*

Superintending Engineer (IT & CRP.)

R. R. No 3925 14/11/08

XEN(IT/CRP) 10/11/08 PA