

JPR5-170

**Jaipur Vidyut Vitaran Nigam Limited**

Office of The Chief Engineer (Comml. & Planning)

No. JPD/CE(C&P)/SE(C)/XEN (RA&R)/F. 2(58)/D. 412


Jaipur Dated 11.03.04

**ORDER**

**Sub:-Installation of GO switches and Horn Gap fuses for Connections to be released on 11KV and higher voltage.**

It has been observed that there are very large number of interruptions on the industrial feeders. These are mainly due to non-availability of GO switches and Horn Gap fuses for the connections released on 11KV, voltage which results in reflection of consumer's faults on Nigam's system. Further, at the time of release of new connections and also for the purpose of maintenance works, due to lack of GO switches too many interruptions are resulting on various feeders of Industrial area(s).

To circumvent the above difficulties it has been decided during course of discussions in the meeting of Executive Engineers of Industrial Areas that henceforth GO switches and Horn Gap Fuses should invariably be provided at the point of tapping of supply to consumers on 11KV and higher voltage. The GO switches and Horn Gap Fuses for existing consumers should be provided by Nigam at its cost in a phased manner. However the same are to be provided at prospective consumer's cost at the time of release of new connections.



(S.C. Malhotra)

Chief Engineer (Comml. & Planning)